6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities for restoring Kattarigatta tank, Registered No. 72—113, Channarayapatna Taluk.

Items of works.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yd.	14,014
Turfing	S. yd.	10,877
Removing and re-fixing grade stones	Each.	29
New Index stones	,,	29
B. M. stones	,,	2
Registered number stone	,,	1
Date stone	,,	1
Gauge stone	,,	2
Rough stone work, new	C. yd.	2,344
Do old	,,	703
Gravel backing	,,	1,232
Sluice—		
Blocking up the old left sluice and constructing new one ..	Lump	sum.
Waste Weir left—		
Earthwork	C. yd.	59
Burnt brick in surki mortar	C. ft.	601
Burnt stone slabs	S. ft.	135
Plastering with surki mortar	Sqr.	2·90
Dry stone in chunam	C. ft.	160
Rough stone work, old	C. yd.	87
Do new	,,	53
Jelly filling under apron	,,	66
Earthwork ramp	,,	26
Turfing	Sqr.	7·00
Waste Weir right—		
Earthwork	C. yd.	59
Burnt brick in surki mortar	C. ft.	787
Burnt stone slabs	S. ft.	203
Plastering with surki mortar	Sqr.	3·42
Rough stone, work new	C. yd.	50
Earthen ramp	C. yd.	33
Turfing	Sqr.	18·00
Constructing silt dams—		
No. i —Earthwork	C. yd.	294
Rough stone work	,,	143
Jelly filling	,,	56
No. ii—Earthwork	,,	260
Rough stone work	,,	138
Jelly filling	,,	97
No. iii—Earthwork	,,	44
Rough stone work	,,	53

C. A. MAHADEVA SASTRI, *Executive Engineer.*

SHIMOGA DIVISION.

Notice dated 10th December 1904.

The 2nd class travellers' bungalow at Augumbi is closed for the public till further notice as the roof of the bungalow is burnt on the night of 6th instant.

K. KRISHNIENGAR, *Executive Engineer.*

KADUR DIVISION.

Notice.

The public is hereby informed that the travellers' bungalow at Balehole in Mudgere Taluk of Kadur District, is not available for occupancy.

Notice.

The attention of the public is invited to the notification in the Gazette of 8th instant calling for tenders for the work of constructing a masonry bridge of 5 arches of 50 feet span across the Bhadra river at Magundi, Koppa Taluk.

H. J. MOLLOY, *Executive Engineer.*